

```
enable
show sp
configure terminal
hostname Layer2Switch-4
interface gigabitethernet1/0
spanning-tree portfast
exit
interface gigabitethernet1/1
spanning-tree portfast
exit
spanning-tree uplinkfast
spanning-tree backbonefast
exit
```